



# **Metropolitan Water Reclamation District of Greater Chicago**

Welcome to the April Edition  
of the 2025 M&R Seminar Series

## NOTES FOR SEMINAR ATTENDEES

- Remote attendees' microphones are muted at entry to minimize background noise.  
**For attendees in the auditorium, please silence your phones.**
- A question and answer (Q/A) session will follow the presentation.
- For remote attendees, please use **"Chat"** only to type questions for the presenter. For other issues, please email Pam to [SlabyP@mwr.org](mailto:SlabyP@mwr.org).  
**For attendees in the auditorium, please raise your hand and wait for the microphone to ask a verbal question during the Q/A session.**
- The presentation slides will be posted on the MWRD website after the seminar.
- This seminar has been approved by the ISPE for one PDH and approved by the IEPA for one TCH. Certificates will be issued only to participants who attend the entire presentation.

**Steven C. Baytos, IV**  
**Water Reclamation Facility Superintendent**  
**City of Akron Water Reclamation Facility**  
**Akron, Ohio**



Steve Baytos has been a Certified Wastewater Operator since 1998. He was promoted to Plant manager in Elyria, where he achieved his Class IV Certification in 2012. He also has a Class III Water Supply Certification. Steve has a Bachelor of Science in Environmental Science from Youngstown State University and a Masters of Public Administration from Ohio University. Currently, he is the Superintendent of the City of Akron's Water Reclamation Facility.



**Joseph M. (Mike) Starkey, P.E.**  
**Project Manager**  
**Burgess & Niple**



Mike rejoined Burgess & Niple in 2017 as a project manager. He previously was a member of the Burgess & Niple team from 1997 to 2006, before moving to Iowa for 11 years. He has a Bachelor of Science in Mechanical Engineering from West Virginia Institute of Technology. His background includes the design of water and wastewater plant improvements, pump stations, rate studies, funding and collections and distribution systems. He is experienced with a wide variety of municipal water and wastewater projects. Mike served as the Technical Lead / Assistant Project Manager for the BioCEPT Improvements Project.





burgessniple.com



# Biological Chemically Enhanced Primary Treatment (BioCEPT) Compared to Traditional Activated Sludge Secondary Treatment During Wet Weather Flows

Steve Baytos  
City of Akron

Mike Starkey, PE  
Burgess & Niple

**METROPOLITAN WATER RECLAMATION  
DISTRICT OF GREATER CHICAGO**

**MONITORING & RESEARCH SEMINAR SERIES**

**APRIL 25, 2025**



# Agenda



Background

Project Scope & Design Approach

Design & Construction  
Challenges

Demonstration Testing

Results



# Consent Decree (CD)

- Akron is in the process of implementing its long-term control plan (LTCP) over a 19-year period to satisfy requirements of a consent decree by 2027.
- Estimated program cost is \$1.2 billion.
- Akron was required to construct a high-rate treatment system with biological component.
- Provide equivalent secondary treatment for all flows up to 280MGD.






# Consent Decree (CD)

- 25 of 27 projects are completed.
- Ohio Canal Interceptor Tunnel.
- North Side Interceptor Tunnel – being built.
- EHRT – Enhanced high-rate treatment facility at the end of the OCIT. Legal process with alternate projects.






# Original Treatment Capacities (2012)






# A Phased Approach (at WRF)





# Current Process Capacities (2022)





# Program Impact on Secondary Bypass

<b>Secondary Treatment Capacity (MGD)</b>	<b>Bypass Events (No./Year)</b>	<b>Bypass Volume (MG/Year)</b>
Original Configuration (110 mgd)	36	962
Phase 1 Expansion: Minimum (130 mgd)	33	620
Phase 2: Enhanced LTCP (220 mgd)	5	41
BioCEPT (280 mgd)	0	0

# Agenda

An aerial photograph of a wastewater treatment plant. The image shows several large circular aeration tanks arranged in a row, along with various industrial buildings and infrastructure. The background is a light blue sky. The text 'Agenda' is overlaid in the top left corner.

Background

**Project Scope & Design Approach**

Design & Construction  
Challenges


Demonstration Testing

Results



# SRT MODIFICATIONS

- 4 MG NOMINAL STORAGE
- OLD IMhoff TANKS
- OFF-LINE STORAGE FOR QUESTIONABLE WWTR SLUGS



Influent Channel

Mag Meters and Splitter box

ACTIVATED SLUDGE

BIOCEPT INFLUENT CHANNEL / CONDUIT

INFLUENT CHANNEL

**BIOCEPT SYSTEM & OPERATIONS BUILDING**

- 10 MG NOMINAL STORAGE BETWEEN TWO TREATMENT TANKS/SYSTEMS
- 60 MGD HIGH RATE TREATMENT (30 MGD EACH SYSTEM)

**TO BIOCEPT**

**METER VALVE**


- FOUR (4) MAG METERS

**TO DISINFECTION**

**TO DISINFECTION**




# South End: New Influent Channel, OLS Tanks, Influent Metering, & Flow Splitter Structure





# North End: BioCEPT Treatment Facility & Storm Detention Basin






# What is BioCEPT?

- BioCEPT is a high-rate, suspended growth contact wet-weather treatment process that combines:
  - Biological Contact Zone
  - Chemically Enhanced Primary Treatment (CEPT)
    - Primary settling with coagulant and polymer addition
    - Significantly increases effective surface overflow rate
- Goal is to provide treatment equivalent to Secondary Treatment.
  - BioCEPT Effluent Requirement per consent decree is 25 mg/L CBOD<sub>5</sub> and 30 mg/L TSS.
  - E.coli limit at plant outfall is 126 MPN/100 mL




# BioCEPT – The Process





# BioCEPT Treatment Facility





# Agenda

An aerial photograph of a wastewater treatment plant. The image shows several large circular aeration tanks arranged in a row, along with various industrial buildings and infrastructure. The background is a light blue sky. The text '© 2014 Google' is visible at the bottom of the image.

Background

Project Scope & Design Approach


**Design & Construction  
Challenges**

Demonstration Testing

Results



# Design & Construction Challenges





# Design and Construction Challenges



## Design Challenges

1. Adding Biosolids ahead of CEPT
2. Building through the “HEART” of the Facility
3. Handling captured solids after an event

## Construction Challenges

1. Expedited Schedule
2. Soil Conditions



# Design Challenges: Adding Biosolids ahead of CEPT

- Evaluation of MLSS concentration and detention time
- Limited Volume of RAS available for treatment of wet weather flow without impacting secondary treatment process
- Used BioWIN modeling and worked with process design engineers for Step Feed Phase 2 Project
  - BioCEPT = 500 mg/L MLSS, 40 min detention
  - $\leq 80,000$  +/- lbs of AS can be pumped to BioCEPT before negatively impacting secondary




# Design Challenges: Building through the “HEART” of the Facility







# AN ORGANIZED & STAGED PLAN OF ATTACK

- 27 page of Sequence of Construction showing the 5 stages of flow through the construction project.
- Use of bulkheads and channel re-routes to achieve continuous flow through the plant during the different stages of construction.
- Coordination with Contractor






# Design Challenges: Dealing with Accumulated Solids within the CEPT Tanks





# Design Challenges: Dealing with Accumulated Solids within the CEPT Tanks





# Tipping Buckets





# Tipping Buckets





# Tipping Buckets





# Construction Challenges: Expedited Schedule

- Bid March 2019
  - Engineer's Estimate: \$68.5 million
  - Bid: \$60.8 million
  - Final Project Cost: \$68.3 million (Soil Conditions)
- Contractor: The Great Lakes Construction Co.
- Construction Management Team:
  - Accenture (formerly Anser Advisory) – Lead Overall Construction Manager for Headworks & BioCEPT
  - G. Stephens Inc. – Construction Manager for BioCEPT
  - B&N – Design Engineer for BioCEPT
- Start Date: May 31, 2019
- Original Final Completion: Sept 29, 2021 (28 months)
- Fully Operational: December 27, 2021 (31 months)



# Teamwork Makes the Dreamwork

- Communication and Teamwork
- TGLCC, WRF Personnel, & CM all working towards the same end goal
- Owner coordinated with contractor over partial flow outages, wet weather events, and full flow outages
- Ohio Canal Interceptor Tunnel
- Outage Coordination



# Construction Challenges: Soil Conditions (increased Soil Anchors)

- Original Count: 540
- Original Design Load: 142 KIPS
- Final Count: 1,255 (added 715)
- Final Design Load: 80 KIPS
- Schedule Impact: 132 days
- Total Cost Impact: \$2.9M





# Agenda

An aerial photograph of a wastewater treatment plant. The image shows several large circular aeration tanks arranged in a row, along with various industrial buildings and infrastructure. The background is a light blue sky. The text 'Agenda' is overlaid in the top left corner.

Background

Project Scope & Design Approach

Design & Construction  
Challenges

**Demonstration Testing**

Results



# Demonstration Study

- Twenty (20) total wet weather events triggered when plant flow  $>110$  MGD
- Treatment Effectiveness Study
- Comparative Study
- Interim Reports 48-hours following receipt of data.
- Final Report due 60 days following last event.





# Demonstration Study parameters

## Field Parameters

- Air Temperature
- Dissolved Oxygen (DO)
- Flow Rate
- pH
- Turbidity
- Water Temperature
- Total Chlorine Residual  
(as applicable)

## Treatment Effectiveness Study

- Total Suspended Solids (TSS)
- Carbonaceous Biochemical  
Oxygen Demand (CBOD<sub>5</sub>)
- *E. coli*


## Comparative Study

- Alkalinity
- CBOD<sub>5</sub>
- Chemical Oxygen Demand
- *E. coli*
- Phosphorus
- Soluble BOD (sBOD)
- Total Suspended Solids (TSS)
- *Campylobacter*
- *Cryptosporidium* and *Giardia*
- *Salmonella*
- Fecal Coliform
- Enterococcus
- Coliphage






# TREATMENT EFFECTIVENESS STUDY SAMPLING PLAN



Sampling Location	Label Code
BioCEPT Influent / Main Plant Primary Influent	T1
BioCEPT Effluent	T2
Combined, Disinfected BioCEPT Effluent and Main Plant Secondary Effluent at Outfall 001 (Only during disinfection season)	T3



# COMPARISON STUDY SAMPLING PLAN



Sampling Location	Label Code
BioCEPT Influent / Main Plant Primary Influent	C1
BioCEPT Effluent	C2
BioCEPT Effluent for bench top sodium hypochlorite disinfection	C3
Main Plant Secondary Effluent (602 location)	C4
Main Plant Secondary Effluent for bench top sodium hypochlorite disinfection	C5




# Sample Analyses



- Pathogen analyses
- 10+ hr drive



- Akron WRF Lab
- Traditional water quality parameters





# Issues / Challenges

- Process a lot of samples in a short time.
- One full three round event produced 145 analytical results, in addition to 56 field data points.





# Issues / Challenges

- 24/7/365.
- Storms seem to happen early evening that results in test events late evening, early morning.
- Pathogen lab not normally staffed after hours for sample delivery.





# Agenda

An aerial photograph of a wastewater treatment plant. The image shows several large circular aeration tanks arranged in a row, with various buildings and infrastructure around them. The background is a light blue sky. The text 'Agenda' is overlaid in the top left corner.

Background

Project Scope & Design Approach

Design & Construction  
Challenges

Demonstration Testing

Results




# Results

Parameter	Row 18 Performance Criteria 30-day Average	BioCEPT Effluent Average thru Event #20
CBOD <sub>5</sub> , mg/L	25	6.3
TSS, mg/L	30	6.5
E.coli, MPN/100mL	126	9.7 Geo Mean




# TSS Percent Removal

## TSS Percent Removal





# CBOD<sub>5</sub> Percent Removal






# sBOD<sub>5</sub> Percent Removal

## Comparison of sBOD<sub>5</sub> Percent Removals

■ BioCEPT Removal %    ■ Traditional Secondary Removal %





# Pathogen results

- Both disinfected BioCEPT and Secondary Effluent (SE) statistically reduced the pathogens analyzed, some as much as a 5-log reduction.
- BioCEPT “outperformed” the SE on coliphage, enterococci, *Cryptosporidium*, and *Giardia*.
- BioCEPT and SE performed similarly on *Campylobacter*, *Salmonella*, fecal coliform, and *E. coli*.
- Overall, the BioCEPT treatment system performed comparably to the parallel Activated Sludge Secondary Treatment process.



*Enterococci*



# Miscellaneous Photos: Influent Channel, Offline Storage & Transition Structure





# Miscellaneous Photos: Primary Settling and BioCEPT Influent Splitter Structure





# Miscellaneous Photos: BioCEPT Inlet Gates & Mixer





# Miscellaneous Photos: Polymer Feed Systems





# Miscellaneous Photos: Coagulant (PAC) Storage Tanks





# Miscellaneous Photos: CEPT Tanks Perforated Baffle Wall





# Closing thoughts...

- Overall, BioCEPT performed comparable to the WRF's activated sludge secondary treatment process.
- Soluble BOD reduction is indicative of the biological treatment occurring within the treatment process.
- BioCEPT under the correct conditions is a HRT system capable of providing the equivalent of secondary treatment for intermittent peak flows.
- The largest benefit of BioCEPT is that it can be started/stopped quickly for wet weather events without concern of how to keep needed biomass alive until the next event.



# ***THANK YOU! ANY QUESTIONS?***



**Steve Baytos**  
**City of Akron**  
SBaytos@AkronOhio.gov



**Mike Starkey**  
**Burgess & Niple**  
Mike.Starkey@BurgessNiple.com